

**RUTH LAKE HYDRO
BILL OF MATERIAL**

Part Description	Count	Part Number	Description	DESIGNATION
Door	1	71 1/4" X 25 3/4"	New Hinged Door	Gen Protection
FT-14 Test Switches (CT/PT)	8	FT4A14T08CN4067	Test Switches	TS1 thru TS8
700G Relay	2	0700GT1A2X0X75850330	X Winding, Y Winding, 8 DO	G1 PRI, G2 PRI
700G Relay	2	0700GT1A2X9X75850330	X Winding, Y Winding, 8 DO, RTD	G1 BU, G2 BU
Crompton Integra 1540 Meter	3	INT-1544-120-5-M-M	Panel Meter	G1 - G2 - BUS
Blank Plates	28	TBD	Blank plates to cover meter/relay removal	
Terminal Board	1	10 Terminal	New TB for Gen Protection Pnl LS	R1

Electrical Reliability Services Protection and Control	TITLE		
	Bill of Material		
	CLIENT	SITE	REF. NO.
	HBMWD	Ruth Lake Hydro	1028255
	ENGINEER	DATE	DRAWING NO.
	M.WALTON	6/28/18	NA